

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montcalm County
(County)

Located In:

Corner Code ##

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------|
| 1. Public Land Survey | T | <u>12N</u> | R | <u>5W</u> | B-9 |
| | T | <u>12N</u> | R | <u>5W</u> | B-11 |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on February, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	●											
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-9: Corner established by U.S. Gov't Deputy Surveyor J. Hodgson in 1837 - accessories: Beech 10, S50W, 12; Pine 12, N74E, 28. Corner recorded under Act 74, PA 1970 in LCRC Liber 1 Page 502 by R. Crater (RLS16924) as "Found 2" pipe - accessories: Power Pole, S60W, 144.30' - Power Pole, S50E, 111.10'" and LCRC Liber 2 Page 271 by W. Tingley (RLS30104) as "Found 2" iron pipe."

B-11: Corner established by U.S. Gov't Deputy Surveyor J. Hodgson in 1837 - accessories: B. Ash 14, S2W, 15; Elm 10, N31-1/2W, 22. County Surveyor J.F. Daoust in 1905 records "Relocated at intersection of N & S 1/4 line (as determined by S 1/4 post and C 1/4 post of Section 31) and N line Section 31 (as determined by NE corner and 1/8 post on N side NE 1/4 Section 31). Drove gas pipe - accessory: Large stone (x) is N18-1/2E, 24-1/2."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9: Found 2" iron pipe and no accessories recovered. Accepted this corner as the best evidence of the original GLO corner.

B-11: Found 3/4" iron pipe - accessory not recovered - agreeing with County Surveyor Record distances to corners A-11 and C-11. Accepted this corner as the best evidence as the original GLO corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9: Found 2" iron pipe
 S64E 111.02', Nail & Depart. of Nat.
 Res. tag in Utility pole
 S53W 71.12', N&T in 10" Pine
 S40E 25.91', N&T 6" Poplar
 N78E 153.12', N&T in 8" Elm

B-11: Found 3/4" iron pipe and inserted 1/2" capped rerod
 N35W 22.36', N&T in 10" Ash
 S28W 32.69', N&T in 14" Oak
 S32E 1.33', N&T in 12" Ash
 N34E 21.54', N&T in twin 9" Ash



Signed by Gary C. Bilow Date 5/12/91
 Surveyor's Michigan License No. 26453