

# SURVEY & REMONUMENTATION MONTCALM COUNTY REMONUMENTATION PROGRAM

Corner approved by Peer Group on \_\_\_\_\_, 1994

AUG 31 1994

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

### COMMISSION

For corners in

Montcalm  
(County)

Located In:

Corner Code #

- |                                       |         |             |            |                |
|---------------------------------------|---------|-------------|------------|----------------|
| 1. Public Land Survey                 | Sec 9   | T <u>12</u> | R <u>5</u> | E-5, SW Corner |
|                                       |         | T _____     | R _____    | _____          |
|                                       |         | T _____     | R _____    | _____          |
|                                       |         | T _____     | R _____    | _____          |
| 2. Property Controlling<br>in Section | S _____ | T _____     | R _____    | _____          |
|                                       | S _____ | T _____     | R _____    | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ | T _____     | R _____    | _____          |
|                                       | S _____ | T _____     | R _____    | _____          |

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

17 AUG 94 3:48 P.M.

VIRGINIA L. KNEPPER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, William Tingley a field survey on June 21, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
November 1838, Enoch Hammel, Deputy Surveyor, GLO Notes

Set Post

Pine 32" S64°E 5 links  
Beech 12" N08°W 13 links

April 1900, H.M. Caulkin, County Surveyor, Book 3, Page 18  
Found pine stump Bearing Tree and took new Bearing Tree

Pine Stump 22" S42°E 42-1/2 feet

April 1905, J.F. Daoust, County Surveyor, Book 4, Page 124

Found stake and New Bearing Trees agreeing

Drove gas pipe, 4 feet long

Pine Stump 22" S41-1/2°E 42-1/2 links

November 1905, J.F. Daoust, County Surveyor, Book 3, page 146

Same as above.

February 1907, J.F. Daoust, County Surveyor, Book 3, Page 254

New Bearing Tree: Pine Stump (cut very low) 24N 41-1/4°E 62-1/4 links

May 1977, D.E. Hunter, No. 19177, Liber 502, Page 496

Found Monument Box

Centerline 18" tree S60°W 70.5 feet  
Cable Box N45°W 59.6 feet

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1-1/4" Gas Pipe -- No Monument Box

Found Nail Northeast side Power Pole N60°W 100.68 feet

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Corner and Monument Box

Cable Box N45°W 59.6 - 58.8 feet to center  
Tree 18" S60°W 70.50 feet (no nail)

Set Nail & Tag North side 20" Maple S60°W 70.86 feet

Nail Northeast side Power Pole N60°W 100.68 feet

LIBER 3 PAGE 117

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date \_\_\_\_\_, 1994  
Surveyor's Michigan License No. 30104

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD July 29  
William Tingley  
William Tingley, PS, Chairman

