


JAN 20 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm (County) Located In: Home Township Corner Code #
1. Public Land Survey Sec 29,32 T 12N R 6W D-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, William G. Tingley a field survey on October 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. November 5th 1837, John Milroy, Deputy Surveyor, G.L.O. Notes. West corrected between section 29 + 32 40.0 Set 1/4 Section post Maple 10 N52°W 20 Links Beech 14 S26°E 18 Links
2. September 3rd, 1879, H. M. Caukins, Red County Surveyor book in the Courthouse. Same as G.L.O.
3. No Date, R.D. McNutt, County Surveyor, Note Card Record #108. 1/4 po. 29-32 Maple 10 N52°W 20 Links Beech 14 S26°E 18 Links 1879 Pine 24 N57°W 8 Links
4. 9/25/73, John R. Radcliff, #11368, L.C.R.C. Liber 1, Page 132. T12N-R6W, D11 Found "T" Iron 48" Oak S05°E 35.72 Feet 36" Oak S35°E 42.11 Feet 36" Box Elder N05°E 39.27 Feet
5. 8/23/73, Fluharty Engineering, Inc., Property Survey. S1/4 Cor. Sec. 29, T12N-R6W, Mich. 4.0' Oak S05°E 35.72 Feet 3.0' Oak S35°E 42.11Feet 3.0' Box Elder N05°E 32.27 Feet
6. October 15, 1979, Richard J. Crater, #16924, Certificate of Survey, Liber 523, Page 216. S1/4 Cor. Sec. 29, T12N-R6W (Recorded Liber 1, Page 133)

Table with 13 rows and 12 columns (A-L) containing numbers 1-36 in a grid pattern.

ACCEPTED BY THE MONTCALM COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 11/29/99

W. SGT William Tingley, PS, Chairman



(Continued on Back...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at the apparent location of the corner and found 1.8" "T" Iron with few small stones, Dug 3' below surface found nothing else. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11: Town 12 North, Range 06 West, Home Township, Montcalm County, Set standard remonumentation pipe in place of "T" Iron: Witnessed By: (M) measured (R) recorded
Set Nail Tag #30104 48" Oak (M) S05°E (R) S05°E (M) 35.80' (R) 35.72'
Set Nail & Tag #30104 36" Oak (M) S40°E (R) S35°E (M) 42.60' (R) 42.11'
Southeast Corner Pole Building (M) N40°E (M) 134.00'
Southwest Corner Pole Building (M)N40°W (M) 133.80'

Bearings given are magnetic. Standard monumentation consists of a Berntsen stainless steel 30" x 2 3/8" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION", P.S. 30104.

Signed by William Tingley Date 22 Dec, 1999
Surveyor's Michigan License No. 30104



(Continued From Section A, D-11, T12N - R 1)

- | | | | |
|----|--|-------|-------------|
| 7. | 3/13/91, Stanley J. Kass, #34972, L.C.R.C. Liber 3, Page 002,
T12N-R6W, D11 Found "T" Iron | | |
| | SW Building Corner (Set) | N35°W | 133.65 Feet |
| | Power Pole (Set) | North | 94.30 Feet |
| | 36" Oak (Found) | S35°E | 42.67 Feet |
| | 48" Oak (Reset) | S05°E | 35.72 Feet |
| 8. | August 13, 1991, William G. Tingley, #301104, Certificate of Survey.
S1/4 Cor. Sec. 29, T12N-R6W Fnd "T" Iron | | |
| | 48" Oak | S05°E | 35.72 Feet |
| | 36" Oak | S35°E | 42.11 Feet |
| | 36" Box Elder | N05°E | 39.27 Feet |
| 9. | No other references found. | | |

RECORDS SECTION

JAN 20 2000

SECTION

