

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
MONTCALM

	(County)	Located In:	Corner Code: //
1. Public Land Survey	T 10N R 5W		C4
	T 10N R 5W		D4
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, GARY C. BILOW, in a field survey on June 11, 1991, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	●	●	9	10	11	12					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(C-4) CORNER PREVIOUSLY RECORDED BY GLEN HACKBARDT, R.L.S. #25844 IN 1981, AND LARRY BRYAN, R.L.S. #25832 IN 1990, AS FOUND 2 1/2" PIPE. BRYAN'S ACCESSORIES, APPEARING ON LAND CORNER CERTIFICATE IN LIBER 2, PAGE 317, ARE AS FOLLOWS: FOUND 40D NAIL & FLAGGING WEST SIDE 12" OAK, NO2E, 76.82', FOUND ELECTRIC FENCE INSULATOR WEST SIDE 18" HICKORY, SOUTH, 122.95', SET NAIL & TAG SOUTH SIDE 12" CHERRY, EAST, 170.45'.

(D-4) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. SHOWN ON RECORDED PLATS "STONES PARK, CRYSTAL LAKE" (DATED 1922) AND "CRYSTAL SHORES" (DATED 1927), RECORDED IN LIBER 3 OF PLATS, PAGE 17, AND LIBER 4 OF PLATS, PAGE 34, RESPECTIVELY. CORNER RECORDED IN 1981 BY GLEN S. HACKBARDT, R.L.S. #25844 AS MONUMENT BOX CHECKING WITH PLAT TO EAST. HIS ACCESSORIES: CL MH COVER S. 76.3', SW COR. HSE S45E 54.46', NW COR. HSE S87E 42.72', C.P. S85W 28.27'. SEE LAND CORNER CERTIFICATE IN LIBER 1, PAGE 544.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-4) FOUND AND ACCEPTED 2 1/2" IRON PIPE AT INTERSECTION OF FENCE LINES NORTH AND EAST. RECOVERED BRYAN'S TIE TO EAST, A NAIL OVERGROWN IN AN 8" & 10" TWIN CHERRY, AT RECORD BEARING AND DISTANCE. BRYAN'S TIE TO INSULATOR IN HICKORY IS OVERGROWN BUT APPEARS TO CHECK.

(D-4) FOUND AND ACCEPTED A 1/2" IRON BAR WITH CAP #21781 IN A MONUMENT BOX AND IN ACCORD WITH RECORD ACCESSORIES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-4) FOUND 2 1/2" IRON PIPE S02W 123.20' SET NAIL AND MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN WEST FACE 9" HICKORY; N40E 1.51' SET NAIL AND MDNR TAG IN SE FACE 3" BASSWOOD; NO2E 49.79' SET NAIL AND MDNR TAG IN WEST FACE 7" CHERRY; EAST 170.48' SET NAIL AND MDNR TAG IN SOUTH FACE 8" & 10" TWIN CHERRY.	(D-4) 1/2" CAPPED IRON BAR IN MON. BOX CL MH COVER SOUTH 76.3'; S48E 54.48' SW COR. HSE; S75E 42.56' NW COR. HSE; S85W 28.25' PK NAIL IN SOUTH FACE POWER POLE; WEST 12.00' SET 4" DIAMETER CONCRETE MONUMENT WITH CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET.
--	---



Signed by Gary C. BiLOW Date 8/15/91  
 Surveyor's Michigan License No. 26453

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

~~PAGE 143~~

PAGE 31