

**SURVEY & REMONUMENTATION**

361 ✓

**FEB 19 1999**

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

**SECTION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm (County) Located In: Cato Township Corner Code # A-9 ✓  
M-9

1. Public Land Survey Sec T 12 N R 8 W  
 T 12 N R 9 W  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 MONTCALM COUNTY  
 RECORDED  
 17 DEC 1998 2:13:43 PM  
 LORI A. WILSON  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on November 30, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1838, John Hodgson, Deputy Surveyor, GLO Notes  
 Set Post Corner, Sections 24 and 25  
 Beech 12" S86°W 34 links  
 Beech 11" N55°W 68 links
  - 1887, H.M. Caukin, County Surveyor, Liber 1, Page 409, Record of Minutes of Survey  
 Found Stone with a Cross on Top.
  - 1925, R.D. McNutt, County Surveyor, Card File Records  
 Stone with "X"  
 Oak 18" Northeast 40 feet  
 Oak 18" N10°E 88.4 feet  
 Maple 12" Northwest 69.5 feet
  - 1990, W. Tingley #30104, Survey in Section 30, T12N-R8W  
 Found 1" Iron Pipe in Monument Box at intersection of Roads.  
 Underground cable marker S45°E 51.60 feet  
 Set Nail in Southside Power Pole N45°E 54.04 feet  
 Set Nail in Northside Power Pole S45°W 41.67 feet
  - 1990, W. Tingley #30104, LCRC, Liber 2, Page 360  
 Same as above
  - 1991, D. Woods, #25246, LCRC, Liber 3, Page 24  
 Found 1" pipe in Monument Box  
 Power Pole S53°W 41.45 feet  
 Power Pole N40°E 53.95 feet  
 Sign Post N65°E 45.80 feet  
 Cable Marker S56°E 51.80 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 2/19/98.

WGT  
 William Tingley, PS, Chairman



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" x 22" pipe in Monument Box at Road Surface. At 1.5 feet found 1" hex-bolt in top of 2" x 14" Pipe. At 2.15 feet deep found stone (6" x 8" x 14") on North Side of Iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set Remonumentation Monument over Pipe and Stone.  
 Power Pole S53°W 41.45 feet  
 Power Pole N40°E 53.95 feet  
 Sign Post N65°E 45.80 feet  
 Cable Marker S56°E 51.80 feet

Liber 4 Page 45

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 2/18, 1998  
 Surveyor's Michigan License No. 30104