

JAN 20 2000

SECTION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montcalm (County)

Located In:

Winfield Township

Corner Code #

1. Public Land Survey

T 12 N R 09W

A-01

T 12 N R 10W

M-01

T 13 N R 10W

M-13

T 13 N R 09W


A-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R



Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 1-13. Row 1: A=6, B=5, C=4, D=3, E=2, F=1. Row 2: A=7, B=8, C=9, D=10, E=11, F=12. Row 3: A=18, B=17, C=16, D=15, E=14, F=13. Row 4: A=19, B=20, C=21, D=22, E=23, F=24. Row 5: A=30, B=29, C=28, D=27, E=26, F=25. Row 6: A=31, B=32, C=33, D=34, E=35, F=36.

I, William G. Tingley, in a field survey on May 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

June 19, 1837 John Hodgson Deputy Surveyor, Set post at intersection corner Townships 12 and 13 North, Ranges 9 and 10 West. Black Oak 28" S28°W 34 links (22.44 feet), Beech 12" N72°E 22 links (14.52 feet) R.D. McNutt index Card 12-10 (13) Ne corner Sec. 1, B Oak 28" S79°w 34 links (22.44 feet), Beech 12" N72°E 22 links (14.52 feet) October 22, 1984, Duane F. Wood # 24625, LCRC T12N-R10W M-01, Liber 002 Page101.

Found 3/4 Steel bar

- 16" Maple S30°E 100.05 feet
20" Maple S45°W 33.15 feet
16" Maple N70°W 100.90 feet

July 1, 1987 Duane F. Wood # 24625, Job # 87273

Found 3/4" steel bar

- 16" Maple S30°E 100.05 feet
20" Maple S45°W 33.15 feet
16" Maple N70°W 100.90 feet

May 24, 1999, William G. Tingley #30104, Found 1" iron pipe 0.5 feet below surface. Found drag tooth 1.0 feet below surface. Found wood stake 1.4 feet below surface 0.2 feet WSW of top of pipe, all are marking wood stake.

- Found nail NW side 14" Basswood S45°W 32.95 feet
Found nail South side 14" Maple N65°W 100.66 feet
Set nail & tag SW side 8" fence post S50°E 45.60 feet
Stop sign post N40°W 45.45 feet

May 24, 1999, William G. Tingley #30104 Found Mecosta Co. Remonumentation monument

- 16" Maple S30°E 100.05 feet
20" Cottonwood w/N S45°E 33.15 feet
16" Maple N70°W 100.90 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Mecosta Co. Remonumentation monument

- 16" Maple S30°E 100.05 feet
20" Cottonwood w/N S45°E 33.15 feet
16" Maple w/nail N70°W 100.90 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Mecosta Co. Remonumentation monument

- 16" Maple S30°E 100.05 feet
20" Cottonwood w/N S45°E 33.15 feet
16" Maple N70°W 100.90 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William G. Tingley Date November 22, 1999

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1973 REVISED MAY 14, 1978 REVISED JAN. 1983 ADAPTED FOR WORD PROCESSING MARCH, 1993

