

**SURVEY & REMONUMENTATION**

MAY 07 1997

COMMISSION

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: Winfield Township Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey Sec 32 T 12 N R 9W E-12, 1/4 Post  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 MONTCALM COUNTY  
 RECORDED  
 12/21/1996 2:09:02 PM  
 VIRGINIA L. KIMMEL  
 REGISTER  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Tingley a field survey on August 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837, John Hodgson, Deputy Surveyor, GLO Notes  
 North between Sections 32 and 33; 40 chains Set quarter Section Post  
 White Oak 24" N43°W 7 links  
 Maple 20" S43°E 14 links  
 No date, R.D. McNutt, County Surveyor, Card File  
 Found plow share, also notched stone and put wooden stake on top  
 Maple 8" N47°E 42 feet

1960, Montcalm County Road Commission - card file record

Road Name Post Southwest 42.80 feet  
 Power Pole Southeast 104.78 feet  
 Maple 20" Northeast 40.84 feet  
 Telephone Pole Northwest 35.96 feet  
 East End Culvert Northeast 42.67 feet  
 West End Culvert Northwest 40.40 feet  
 Found Plowpoint, raised to surface with Boat Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 1 foot bolt in Monument Box  
 Found 1/2" x 1 foot bolt beneath first bolt  
 Found 2 plowpoints and 2 other iron parts coming together at a point at their tops; set in a nest of stones; found a stone (possibly notched) on westside of irons. Accepted point of iron object as corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over pointed irons  
 Set Nail and Tag in Maple 24" N47°E 42.00 feet (probably MCRC 1960)  
 Set Nail and Tag in Maple 26" N30°E 87.93 feet  
 Face of project marker S45°E 42.25 feet  
 Stop Sign Post N35°W 45.44 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 12-17-1995  
 Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19  
 REVISED MAY 14, 197  
 REVISED JAN., 194  
 ADAPTED FOR WORD PROCESSING MARCH, 195



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-17-96  
WGT.  
 William Tingley, PS, Chairman