

RECORDED

JAN 20 2000


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm Located in: _____ Corner Code _____
_____ (County) _____ Township _____

1. Public Land Survey	Sec 13	T <u>12N</u> R <u>09W</u>	<u>L07</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on June 7, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- April 20th, 1838, Abner E. Van Ness, Deputy Surveyor, G.L.O. Notes, page 364.
39.62 Set Qr. Section post
Beech 16" S42°W 15 links (9.90 feet)
Pine 20" N42°E 05 links (3.30 feet)
 - April 20th, 1838, Henry M. Caulkins, County Surveyor Notes, Book 2, page 65.
Section 23, T12N R09W
Reset quarter post North side Section and drove iron 2" pipe 34" long
 - March 24, 1998, William Tingley # 30104, Survey # 97762-001
Set iron and cap at intersection of stump fence and remains of a E-W wire fence
Set nail and tag South side 14" Maple East 9.08 feet
Set nail and tag NE side 18" Maple N45°W 13.60 feet
Set nail and tag South side 14" Maple S80°W 13.19 feet
Set nail and tag West side 10" Maple South 9.77 feet
 - No other references found
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- June 6, 1999, Found 1/2" iron with cap #30104
- | | | |
|---|-------|------------|
| Found nail and tag South side of 14" maple | East | 9.08 feet |
| Found nail and tag Northeast side 18" maple | N45°W | 13.60 feet |
| Found nail and tag South side of 14" maple | S80°W | 13.19 feet |
| Found nail and tag West side of 10" maple | South | 9.77 feet |
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set Remonumentation Monument over 1/2" iron and cap #30104
- | | | |
|---|-------|------------|
| Found nail and tag South side of 14" maple | East | 9.08 feet |
| Found nail and tag Northeast side 18" maple | N45°W | 13.60 feet |
| Found nail and tag South side of 14" maple | S80°W | 13.19 feet |
| Found nail and tag West side of 10" maple | South | 9.77 feet |

ACCEPTED BY THE MONTCALM COUNTY SURVEY PIER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12/17/99

W. Tingley
William Tingley, PS, Chairman



This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William Tingley Date 22 Dec 1999
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



LIBER 4

PAGE 190