

APR 28 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm (County)

Located In: Cato Township

Corner Code #

- 1. Public Land Survey Sec T 12 N R 8 W T 12 N R 9 W T R T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous Property in Sec. S T R S T R

A-9 M-9

STATE OF MICHIGAN MONTCALM COUNTY RECORDED

27 APR 1999 8:27:53 AM

LORI A. WILSON REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, William Tingley a field survey on November 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838, John Hodgson, Deputy Surveyor, GLO Notes

Set Post Corner, Sections 24 and 25

- Beech 12" S86°W 34 links
Beech 11" N55°W 68 links

1887, H.M. Caukin, County Surveyor, Liber 1, Page 409, Record of Minutes of Survey Found Stone with a Cross on Top.

1925, R.D. McNutt, County Surveyor, Card File Records

Stone with "X"

- Oak 18" Northeast 40 feet
Oak 18" N10°E 88.4 feet
Maple 12" Northwest 69.5 feet

1990, W. Tingley #30104, Survey in Section 30, T12N-R8W

Found 1" Iron Pipe in Monument Box at intersection of Roads.

- Underground cable marker S45°E 51.60 feet
Set Nail in Southside Power Pole N45°E 54.04 feet
Set Nail in Northside Power Pole S45°W 41.67 feet

1990, W. Tingley #30104, LCRC, Liber 2, Page 360

Same as above

1991, D. Woods, #25246, LCRC, Liber 3, Page 24

Found 1" pipe in Monument Box

- Power Pole S53°W 41.45 feet
Power Pole N40°E 53.95 feet
Sign Post N65°E 45.80 feet
Cable Marker S56°E 51.80 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 22" pipe in Monument Box at Road Surface. At 1.5 feet found 1" hex-bolt in top of 2" x 14" Pipe. At 2.15 feet deep found stone (6" x 8" x 14") on North Side of Iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over Pipe and Stone.

- Power Pole S53°W 41.45 feet
Power Pole N40°E 53.95 feet
Sign Post N65°E 45.80 feet
Cable Marker S56°E 51.80 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Table with 13 rows and 13 columns (A-M) containing numbers 1-36.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 2/18/98

WGT William Tingley, PS, Chairman

Liber 4 Page 93

Signed by William Tingley

Date 2/18, 1998

Surveyor's Michigan License No. 30104

