

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 19 2000

SECTION

For corners in Montcalm (County) Located In: Reynolds Township Corner Code # _____


1. Public Land Survey Sec. 4, 9 T 12 NR 10 W F-03
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on May 15, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. October 19, 1837, Abner E. Van Ness, Deputy Surveyor, GLO notes, West corrected between sections 4 & 9. Set qt. Section post at 40.10 chains

Pine 22" S42°W 12 links (7.92 feet)
 Pine 24" N33°E 11 links (7.26 feet)

2. December 10, 1903, Henry M. Caukin, County Surveyor, Record of Minutes of Survey, sec 9 T12N R10W

New Bearing Tree
 W. Oak 8" N63 1/4°E 63 links (41.58 feet)

3. November 28, 1988, Burt Wickham Jr., # 17639, LCRC Liber 2 Page 231

Found 1 1/2" Iron Pipe
 Nail Oak 24" N30°W 34.45 feet
 Nail Oak 24" S45°W 36.47 feet
 Nail Elm 10" S05°E 96.33 feet
 In CL Rd South
 CL E-W Rd 4.0' ± South

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/26/00

William Tingley, PS, Chairman

4. April 14, 1993, Burt Wickham Jr., # 17639, Certificate of Survey, Liber 703 Page 678

Found 1 1/2" Iron Pipe in CL Long Rd
 CL Cutler Rd South 4.00 feet ±
 Nail 24" Oak N30°W 34.45 feet
 Nail 24" Oak S45°W 36.47 feet
 Nail 10" Elm S05°E 96.33 feet



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched the apparent location of the corner. Found 1 1/2" Iron pipe. Corner is in C/L of N-S road and 10 feet north of C/L E-W road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left pipe, will monument after the completion of roadwork.
 N/T W/S cor fence post N17°E 14.72 feet
 Fnd Nail S/S P.P. N68°E 37.37 feet
 N/T E/S 20" Oak N06°W 26.73 feet
 SW Cor garage N20°W 112.47 feet
 N/T S/S " Pine N70°W 102.29 feet



LIBER 4 PAGE 325

This corner is accepted as the best available evidence of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William G. Tingley Date 10/26/00
 Surveyor's Michigan License No. 30104