

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS
1994 DEC 29 AM 10:10
RECEIVED FOR RECORD

For corners in

MUSKEGON Located In: Corner Code ##
(County)

1. Public Land Survey T 9 R 15
T 9 R 14
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

A1574

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, STEPHEN V. VALLIER in a field survey on JULY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1837 GLO SET SECTION CAP

1950's MUSKEGON COUNTY ROAD COMMISSION IRON BOLT
NE 51,30' 12" MAPLE
NW 94.40' 12" MAPLE
1983 FOUND CAPPED IRON D. SCHIELE LIBER 1255, PAGE 474
1984 C.F. LEWANDOWSKI LIBER 1301, PAGE 590 SET 4" x 30"
CAST IRON MONUMENT - WITH COUNTY SURVEY CAP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" CAST IRON MONUMENT WITH COUNTY SURVEY CAP
ACCEPTED POSITION OF EXISTING CORNER DUE TO CONFIRMATION
OF OLDEST KNOWN WITNESSES

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 245, OF 1990

May 1, 1994 SV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP
N25 DEG. 59.59' 180 FT USGS
N55 DEG. W 41.64' 180 FT USGS
S45 DEG. W 48.25' NAIL IN GUY POLE
N60 DEG. E 50.94' NAIL IN 28" MAPLE
S45 DEG. E 45.60' POWER POLE WITH NAIL



Signed by [Signature] Date May 1 1994

Surveyor's Michigan License No. 28428