

JAN 31 2001

200 DEC 29 AM 11:22

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: Muskegon (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Mark Fairchild REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Ralph W VanRiper, in a field survey on Nov. 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column B and row 1.

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET BY GLO (N 1/4 Corner of Section 6)
1971, 1976 & 1980 C F Lewandoski found and used "Iron"
1950's Muskegon County Road Commission Witness Sheets shown nothing at this corner
Current Muskegon County Road Commission Witness Book = Iron Pipe : N 30.7' Cable Sign : S 77.15' 4" Maple : SW 131.44' P.P. : N 77.65' Clump of Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe in 2" Pipe over "T" Iron in Centerline of Asphalt Pavement of Sherman Road and Tree line North and South
Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 6/6/2000

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument
S 59° E 70.00' Set Spike in Sly side of Twin 6" Poplar
S 08° W 77.15' Set Spike in E side of 6" Maple
S 70° W 131.46' Found Spike in SE Side of Power Pole
N 63° W 81.93' Set Spike in Slt side of 18" Elm
N 13° W 37.80' Set Spike in Ely side of Twin 12" Elm
North 30.70' Found Center of Cable Sign
North 74.45' Set Spike in E side of 24" Elm

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 365, OF 1990



Signed by [Signature] Surveyor's Michigan License No. 16946

Date 12/26/2000