

JAN 31 2001

LIBER 3121 PAGE 646

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

2001 DEC 20 PM 1:48

For corners in SECTION

Form with fields for Muskegon (County), Located In: T 9N R 14W, Corner Code # B-5, and sections for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Handwritten signature: Mark Fairchild, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Stephen V. Vallier, in a field survey on November 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at row 5, column B.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 John Mullett (G.L.O.) set post.
N 10° E 8" Tamarack 12 Links
S 04° W 9" Tamarack 18 Links

1990 Stan Shackelford of Westshore Consulting found no record of corner being reset since G.L.O. Found a 5/8" x 12" rod over a 5/8" x 36" rod in the centerline of road. Check is within 2' of the G.L.O. proration and is on the occupation line to the South. Reset with a 4"x30" cast-iron "County Survey Monument." Recorded corner in L.C.R.C., Liber 1545, Page 274.

S 80° W 142.61' Power Pole
N 25° W 75.69' Corner Post
N 04° E 105.46' SE Corner Barn
N 58° E 118.05' Power Pole
N 82° E 138.38' Telephone Riser
S 76° E 186.94' Power Pole

POSITION OF SAID Rod found
RECORDED CORNER 10/17/00
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 4" x 30" cast-iron monument with a broken cap was found. Checks with the witness ties of L.C.R.C. recorded in Liber 1545, Page 274. The position of the existing corner, per L.C.R.C., Section B, was accepted.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 4"x30" cast-iron monument with a broken cap found.
S 80° W 142.61' Power Pole Found nail
N 42° W 131.40' SW Corner of Barn
N 04° E 105.46' SE Corner of Barn
N 58° E 118.05' Power Pole Found nail
N 82° E 138.38' C/L Telephone Riser
S 76° E 186.94' Power Pole Found nail



Signed by [Signature]
Surveyor's Michigan License No. 28428

Date 12/19/00

Handwritten file number: A2114