

**SURVEY & REMONUMENTATION**

JAN 31 2001

SECTION

LIBER 3124 PAGE 912

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

200 DEC 29 AM 11: 22

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Mark F. Fischell*  
REGISTER OF DEEDS

For corners in  
Muskegon  
(County)

Located in: Corner Code #

1. Public Land Survey	T 9N R 14W	B-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on Dec. 6, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Quarter Section Post : Maple 26" N8°W 24L : Maple 13" N78°E 49L  
1950's MCRC Witness Sheets show nothing at this corner  
Current MCRC Witnesses Book shows : Iron Bar, CPE (C P Englert): SW 38.28' 10" Osage Orange : NW 41.31' 6" Osage Orange : NNE 26.90' 5" Osage Orange : NE 36.09' 11" Osage Orange  
D W Schiele on Ottawa County LCRC (L 3, P 699) for North 1/4 Corner of Sec. 6, T8N, R14W, shows South 1/4 Corner of Sec. 31 as (S 90° W 59.07') of North 1/4 Corner of Sec. 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Capped Rod # 18987 ( C P Englert), 3' North of Centerline of Gravel of Wilson Road and Tree Line to the North

Historical usage, documentation and evidence of corner location review and ratified by Muskegon County Peer Group 8/11/2000

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 74 OF 1970  
*RWR*  
*8/11/00*



C. Description of monument for corner and accessories established to perpetuate locating the

- Set 2 3/4" Cast Iron "County Survey" Monument
- N 40° W 41.11' Found Spike in SW side of 10" Osage Orange
- N 13° E 29.48' Found Spike in W side of 9" Osage Orange
- N 60° E 57.30' Set Spike in Sly side of Twin 8" Osage Orange
- S 08° E 63.74' Set Spike in E side of 10" Pine
- S 60° W 68.22' Set Spike in NW side of 8" Osage Orange
- S 37° W 38.73' Set Spike in NW side of 10" Osage Orange
- East 59.07' Found Broken Ottawa County Monument

Signed by Ralph W. Van Riper  
Surveyor's Michigan License No. 16946

Date 12/26/00