

JAN 31 2001

LIBER 3124 PAGE 913

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

2001 DEC 29 AM 11: 22

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mark F. Fairchild
REGISTER OF DEEDS

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 14W	C-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Nov. 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set-Post Corner Section 5 & 6 : Beech 12" S24°W 35L
C F Lewandowski Found "Iron" in 1972, 1976 & 1980
1950's MCRC Witness Sheet = 2" Stake : NE 39.86' T : SE 85.32' 12" Elm : SW 83.35' P.P.
WNW 94.52' P.P.
Current MCRC Witnesses Book = WNW 68.7' Eastside Cable Marker : ESE 82.25' CL Fence Post :
SE 85.92' T.P. : NE 39.86' T.P. : SE 85.32' 12" Elm : SW 83.45' P.P. : WNW 94.52' P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR Spike in 2" Pipe over 2" Pipe at Intersection of 5 Roads
Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 6/6/2000

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345 OF 1990
RVF
6/6/00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument
S 86° E 331.55' Set Spike in N side of 26" Elm
N 06° W 247.76' Set Spike in E side of Twin 6" Elm
N 86° W 387.15' Set Spike in S side of 26" Ash
S 44° W 45.22' Found PK Nail in Ely side of Light Pole
S 34° W 80.22' Found Spike in SE side of Power Pole
S 12° E 165.93' Set PK Nail in Wly side of Guy Pole



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16948

Date 12/26/00