

JAN 31 2001

SECTION

LIBER 3124 PAGE 914

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD

200 DEC 29 AM 11:22

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Mark F. Fairchild REGISTER OF DEEDS

For corners in

Muskegon

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 14W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on Nov. 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set 1/4 Section Post between Sec. 7 & 8 : Tamk 12" N16°E 10L

1950's MCRC Witnesses Sheets = NE 46.86' T : SE 103.75' S Edge of NW Corn. Transm. Tower  
WNW 35.00' Nail in s End of West tie in R.R. Br.

Current MCRC Witnesses Book = E 8' CL Gravel Rd : W 14.80' Nail in RR Tie SE side brd.  
N 5.55' N edge S rail, same Witnesses as on S H Shackelford LCRC, L 1325, P 709 (1/2" Rod)

1981 C F Lewandoski Set 1/2" Rod from Distance & Witnesses on 1950's MCRC Witnesses Sheets

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Capped Rod (Tru-Line # 27437), 10' W of Center of Gravel Road & 9' S of Center of Bike Path on Old RR R/W

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 6/6/2000

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345 OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Set 2 3/4" Cast Iron "County Survey" Monument

- S 56° E 103.48' NW Corner of Steel Tower
- N 81° E 168.58' Set Spike in S side of 5" Sassafras
- N 65° E 48.43' Set Spike in NW side of Wood Stop Sign Post
- N 33° W 38.03' Set "+" Cut in N end of Concrete Culvert
- S 52° W 26.48' Set "+" Cut in S end of Concrete Culvert
- S 46° W 182.00' Set Spike in Sly side of Power Pole



Signed by Ralph W. Van Riper  
Surveyor's Michigan License No. 16948

Date 12/26/00

A2186