

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in 2000 DEC 20 PM 1:48

2000 DEC 20 PM

<u>Muskegon</u>	Located In:	Corner Code #
<i>Mark Fairchild</i>		
1. Public Land Survey	9N R 14W	C-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Mark Fairchild
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephen V. Vallier, in a field survey on November 11, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	16		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 John Mullett (G.L.O.) set post.
 S 08° E 12" Hemlock 5 Links
 N 20° E 8" Sugar 9 Links

1934 Muskegon County Road Commission found a 4" iron pipe.
 N 45° W No Distance 2" Wood Stake
 SE 40' 2" Wood Stake
 NE 40' 2" Wood Stake
 SW 40' 2" Wood Stake

1950's Muskegon County Road Commission's witness sheet notes a 2" iron pipe.
 ENE 47.7' Mail Box Post
 WSW 34.3' S end of Culvert
 NW 57.92' Power Pole

1990 Stan Shackelford of Westshore Consulting found a 4" x 18" pipe over the remains of a wood stake. Checks with existing witnesses and occupation as found. Reset with a 4" x 30" cast-iron "County Survey Monument" recorded in L.C.R.C., Liber 1545, Page 755.

S 22.75' P.K. nail in W end of culvert
 S 35° W 34.05' "X" in S end of R.C.P. culvert
 S 30° E 193.05' NW corner of house
 N 45° E 39.40' C/L of Telephone Riser
 N 50° W 33.60' "X" in N end of R.C.P. culvert

SURVEY &
 REMONUMENTATION

JAN 31 2001

SECTION

POSITION OF SAID *Reset*
 RECORDED CORNER *11/14/00*
 REVIEWED & RATIFIED *SV*
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 4" x 30" cast iron monument with a "County Surveyors Cap" was found on a fence line to the South. Verified witness with L.C.R.C., Liber 1545, Page 755. Position of existing corner was accepted due to historical usage and documentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 4" x 30" cast-iron monument containing a "County Surveyors Cap" was found.
 S 35° W 33.23' Set "X" mark in S end of culvert
 N 50° W 33.64' Found a "X" mark in N end of R.C.P. culvert
 S 37° E 172.68' Found on NW corner of house
 N 45° E 39.62' Telephone Riser on S side
 N 36° W 57.69' Fence Post Found P.K. nail on E side



Signed by *Stephen V. Vallier*
 Surveyor's Michigan License No. 28428

Date 12/14/00

A2115