

JAN 31 2001

LIBER 3124 PAGE 916

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

2001 DEC 29 AM 11:22

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 14W	C-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Mark Fairchild
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Quarter Section Post = Hemlock 18" S64°E 3L & Hemlock 12" S27°W 13L

1950's MCRC Witness Sheets & Current MCRC Witness Book shows nothing at this corner

T E Joiner & Driesenga & Associates have used a computed point 1/2 way on line between Section Corners C-7 & C-9 for location of 1/4 Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a Caped 1/2" Rod No. 18987 (C P Englert) and Pointed Stone, approximately on line between Section Corners and 17.5' South of 1/2 way between Sections Corners. Fence lines North, South & West

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 7/11/2000

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument

N 10° E 10.76' Found Spike in W side of 6" Sassafras
East 16.88' Found Spike in S side of 14" Poplar
S 20° W 15.45' Found Spike in E side of 10" Poplar
West 12.82' Found Spike in N side of 14" Poplar



Signed by Ralph W. VanRiper
Surveyor's Michigan License No. 16948

Date 12/29/2000

A2188