

JAN 31 2001

LIBER 3124 PAGE 922

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD

200 DEC 29 AM 11: 23

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Mark Fairchild REGISTER OF DEEDS

For corners in

Table with columns: Muskegon (County), Located In, Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Ralph W VanRiper, in a field survey on Nov. 27, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of row 7 and column C.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Quarter Section Post : Pine 15" N40°W 12L & Beech 10" S46°W 14L
3/4" Pipe Set by MCRC in 1930, 2651.45' from Section Corner to the East
1950's & Current MCRC Witness Sheets & Book shows same Witnesses = SE 59.8' Tel. Pole : WSW 46.7' 30" Maple : NW 34.3' 30" Elm Recorded Survey by KJ Roosien in 1990 Found Capped Iron; Fnd Spk NE side P Pole S45°W 47.76' : NE Cor Hse Fnd S50°E 108.05' : Fnd Nail & Tag S side 20" Tri Maple N60°W 61.42' Recorded Survey by M J Rosema in 1993, Found 3/4" Pipe, Nail & Tag S Side 12" Maple WNW 61.40' : NE Cor House Fndn SW 108.03 : NW Cor House Fndn WSW 146.14'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK Nail in Asphalt Pavement over 3/4" Pipe, 1.2' South of Centerline of Asphalt pavement of Ellis Road and Centerline of Gravel of Rollenhagen Road to South

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 7/11/2000

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 2 3/4" Cast Iron "County Survey" Monument
S 18° W 132.23' Set Spike in Wly side of 6" Apple
N 77° W 156.08' Set Spike in Sly side of 26" Maple
N 67° W 132.02' Set PK Nail in NE side of Power Pole
N 04° W 162.53' Set Spike in W side of 6" Maple
S 50° E 47.04' Set Spike in SW side of 6" Wood Fence Post

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345 OF 1990



Signed by [Signature] Surveyor's Michigan License No. 16948

Date 12/26/00