

SURVEY & REMONUMENTATION

JAN 31 2001

LIBER **3124** PAGE **923**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

200 DEC 29 AM 11: 23

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mark Fairchild
REGISTER OF DEEDS

For corners in

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>D-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ralph W VanRiper, in a field survey on Nov. 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Quarter Section Post = Hemlock 8" S23°E 12L & Pine 15" N70°W 10L
1950's MCRC Witness Sheets shows nothing at this corner. Current MCRC Witness Books shows 1" Iron set by J P Clapp in 1972, LCRC, L 1002, P 17 = Quad Maple NW 35.60' : Twin Maple W 24.87' : Twin Maple NE 40.80' F F Smith in 1976 Found Bent Iron & Replaced with 1/2" Rod, NE 16" Maple 40.82' : W. Tw 8" Maple 35.60' : NW Quad Maple 35.60' : E Fence Post 39.04' C F Lewandoski in 1978 Found 1/2 " Rod. K J Roosien in 1990 Found Re Rod J M Nousain in 1998 Found 5/8" Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Rod & 1/2" Rod 0.10' West, 2" West of Centerline of Gravel of Rollenhagen Road and Fence line to the West

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 7/11/2000

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of said corner:

Set 2 3/4 Cast Iron "County Survey" Monument
West 25.29' Found Spike in N side of Twin 14" Maple
S 55° E 52.95' Found Spike in Nly side of 10" Poplar
S 40° W 49.58' Set Spike in NW side of 10" Poplar
N 62° E 32.70' Found Spike in SE side of 6" poplar
N 25° E 76.26' Found Spike in SE side of 10" Poplar
N 42° W 53.15' Set Spike in SW side of 5" oak



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date 12/26/00

A2195