

FEB 09 2000

LIBR 2327 PAGE 695

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

1999 DEC 29 AM 8:37

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 14W	E-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Mark Fairchild*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on July 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	5		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set Quarter Section Post between Sections 16 & 17  
Lynn 12", N59°E, 5L & Lynn 8", N85°W, 4L

Muskegon County Road Commission - Old Witness Sheets shows nothing at corner; Current Witness Book shows - Iron Rod, Mon. Box; S45°E E End Culv 39.30'; ENE T Riser 34.60'; WSW Stump 57.85'; SSW 37.35' Map.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe over 1" Rod in Monument Box in Moorland Road at Hile Road

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 5/11/99

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990  
*SW 5/11/99*

C. Description of monument for corner and accessories established to perpetuate locating the position of the

Set 2 3/4" Cast Iron "County Survey" Monument in Monument Box

- N 60° W 41.51' Set "X" on W end of Concrete Curb
- N 30° W 42.59' Set "X" on N end of Concrete Curb
- N 50° W 57.05' Found Nail in NE side of Wood Fence Post
- S 48° E 39.18' Set "X" in E end of Concrete Culvert
- S 60° W 43.70' Set "X" in W end of Concrete Culvert
- S 52° W 98.65' Found Nail in Nly side of Power Pole



Signed by *Ralph W Van Riper*  
Surveyor's Michigan License No. 16946

Date Dec. 22, 1999