

JAN 31 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2000 DEC 20 PM 1:48

For corners in **SECTION**

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 9 N R 14 W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Mark Fairchild
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Stephen V. Vallier, in a field survey on November 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 John Mullett (G.L.O.) set post.
N 89° W 8" Hemlock 17 Links
N 31° W 12" Hemlock 17 Links

1881 County Survey records show corner being equidistant between E-9 and E-10 of 2642' respectively.

1950's Muskegon County Road Commission's witness map notes an iron pipe.
W 42.03' Fence Post
E 33.56' Fence Post
SW 97.47' Power Pole

Distance: E-10 to E-9 measure is 2627.1'
Distance: E-10 to E-11 measure is 2627.25'

POSITION OF SAID *Restored*
RECORDED CORNER *11/14/00*
REVIEWED & RATIFIED
BY MUSKEGON COUNTY *scw*
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

1982 Muskegon County Road Commission - John Lazarock found a railroad spike over a 1 1/2" iron pipe, which he reset with a 4" x 32" cast-iron monument containing a "County Surveyors Legend" and placed it in a monument box. Corner recorded in L.C.R.C., Liber 1246, Page 12.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 4" x 30" cast-iron monument with a "County Surveyors Legend" placed in a monument box on the occupation line to the East and West. Witnesses verified with LCRC, Liber 1246, Page 12. Position of the existing corner was accepted due to historical usage and documentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 4" x 30" cast-iron monument with a "County Surveyors Legend" was found in a monument box.
N 16° W 148.11' Power Pole Set 20D nail on W side
N 42° E 142.04' SW Corner of Hse. #6218
N 80° W 59.92' 12" Poplar Set 20D nail on N side
S 58° E 39.47' 14" Twin Elm Found spike on SW side
S 25° W 97.25' Power Pole Found spike on W side



Signed by *Stephen Vallier*
Surveyor's Michigan License No. 28428

Date 12/19/00
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1971
REVISED JAN., 1971
REVISED OCT., 1971

A2119