

CORNER RE-LOCATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
LIBER 3121 PAGE 640

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD
 2001 DEC 20 PM 1:11
Mark F. Fairchild
 REGISTER OF DEEDS

For corners in
Muskegon
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>9</u> N R <u>14</u> W | <u>E-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

SURVEY & REMONUMENTATION

4. Lot No. _____, Recorded Plat JAN 31 2001

5. Private Claims _____

SECTION

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, Stephen V. Vallier, in a field survey on November 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 John Mullett (G.L.O.) set post.
 N 39° W 9" Beech 13 Links
 N 23° E 9" Beech 31 Links
- 1982 Muskegon County Road Commission found a 1 1/4" pipe in a monument box.
 NW 51.02' Power Pole
 SW 50.75' NE Corner Church
 SE 77.81' C/L Concrete Marker
 E 26.81' Ottawa County Corner (Sec. 4 and 5)
- 1982 Muskegon County Road Commission set a 4" x 32" cast-iron monument with a "County Surveyors Legend" in a monument box. (L.C.R.C., Liber 1246, Page 13)
 NW 50.98' P.K. nail in Power Pole
 SW 26.89' Chiseled "X" at mid point of concrete curb and gutter.
 SE 56.54' Chiseled "X" at mid point of concrete curb and gutter.
 NE 51.15' Chiseled "X" at mid point of concrete curb and gutter.
 E 26.84' Ottawa County Corner (Sec. 4 and 5)

POSITION OF SAID *Ratified*
 RECORDED CORNER *11/14/00*
 REVIEWED & RATIFIED *sm*
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 4" x 32" cast-iron monument with a "County Surveyors Legend" in a monument box. Verified witnesses with LCRC, Liber 1246, Page 13 Corner lies in the centerline of the existing rods North-South and East-West. Position of the existing corner was accepted due to historical usage and documentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A 4" x 32" cast-iron monument with a "County Surveyors Legend" in a monument box.
 N 52° W 50.97' Found P.K. nail in E side of Power Pole
 S 23° W 26.90' Found "X" in Concrete Curb
 S 58° E 65.48' Found "X" in Concrete Curb
 N 54° E 51.00' Found "X" in Concrete Curb
 E 26.82' Found County Surveyors Monument in Monument Box
 (Closing corner of E-1, T8N, R14W)



Signed by *Stephen V. Vallier*
 Surveyor's Michigan License No. 28428

Date 12/19/00
 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1971
 REVISED JAN. 1, 1973
 REVISED OCT. 1, 1975

A2108