

FEB 09 2000

LINE 2327 PAGE 696

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD 1999 DEC 29 AM 8:37

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Mark Fairchild REGISTER OF DEEDS

For corners in

<u>Muskegon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>F-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		10		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, Ralph W VanRiper, in a field survey on June 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set Quarter Section Post Section 4, T9N, R14W & Section 33, T10N, R14W
Beech 6", N13°W, 18L & Sugar 10", N44°E, 21L

Muskegon County Road Commission - Old Witness Sheets shows - 1/8 X 1 1/2 Bar; N 32.7' 14" Elm SW 65.7', T Pole; NW 75.0' 14" M Current Road Commission Witness; Book shows - Iron Bar; SW 46.55' Angle Iron; NE 81.40 P.P.; N 32.7' 14" Elm; SE 54.0' 16" Elm; SW 43.48' Tel. Pole

1984 Westshore E & S found Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/4" by 1 1/2" by 22" Iron Bar in Gravel of Sherman Blvd. at Wunsch Road

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 5/11/99

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990
5/11/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument

- S 43° E 54.00' Found Nail in NE side of 16" dead Elm
- N 50° E 81.40' Found Nail in SE side of Power Pole
- N 08° E 28.06' Found Nail in E side of Wood Fence Post
- N 70° W 116.27' Set Nail in S side of 12" Elm
- S 12° E 102.70' Set Nail in NE side of 14" Elm
- N 52° W 56.50' Set Nail in SW side of 12" dead Elm



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date Dec. 22, 1999