

SURVEY & REMONUMENTATION

FEB 09 2000

LINE 2327 PAGE 700

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD 899 DEC 29 AM 8:37

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Mark F. Fairchild REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on June 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		10		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO 24" Pine Tree at Quarter Section Corner between Section 9 & 16

Muskegon County Road Commission Old Witness Sheets and Current Witness Book shows: 2" Stake; N 25.2' Elm Cluster; SE 58.23' 12" Elm; SW 85.70' 14" M

1992 S H Shackelford LCRG, L1645, P198: Set 1/2" Rod in Gravel: S 70° W 28" Maple 85.70'; S 47° E Elm Cluster 53.15'; N 72° W Power Pole 142.19'; N 3° W Set 1/2" Rod 40.98'; S 45° E Elm Stump 58.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod in Gravel of Cline Road

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 5/11/99

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1950

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument

- N 03° W 40.98' Found 1/2" Rod
- S 70° W 85.70' Found Nail in SE side of 26" Maple
- S 78° W 125.75' Set Nail in NW side of 28" Maple
- N 73° W 142.19' Found Nail in N side of Power Pole
- S 08° W 55.38' Set Nail in E side of 6" Elm
- S 48° E 53.15' Found Nail in SW side of Elm Cluster



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date Dec. 22, 1999