

SURVEY &
REMONUMENTATION

MAR 09 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1998 DEC 29 PM 4:24

For corners in SECTION

Carrie Carter
REGISTER OF DEEDS

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>14</u> W	<u>G-2-</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FIBER 2189 PAGE 820

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4	●	3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Section 3 and 4, T10N, R14W

Post set by GLO Surveyors in 1837 : Pine 10" S34°W 40L & Pine 8" S65°E 19L

MCRC 1950's Witness Map shows nothing at this corner

Current MCRC Witness Book shows (Fd 1/2" rod @ int. of fences N-S-E-W) by C F Lewandoski 7/15/83 : N10W 18.11' 18" Ash - S35°E 15.30' 16" Map. - S65°W 11.08' 8" Tw. Map.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod and accepted corner based on Historical usage and documentation


sw
7/7/98

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- S 35° E 15.30' Found Spine in S side of 18" Maple
- South 17.29' Found Spike in W side of Twin 12" Ash
- S 65° W 10.99' Found Spike in SE side of Twin 10" Maple
- S 80° W 29.34' Set Spike in S side of 12" Ash
- N 10° W 18.11' Found Spike in SW side of 22" Ash
- N 05° W 21.25' Set Spike in W side of 5" Maple



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16946

Date Dec. 23, 1998

Office

A1997