

MAR 09 1999

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1998 DEC 29 PM 4: 24

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Muskegon
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>14</u> W	G-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Carrie Carter
REGISTER OF DEEDS

LIBER 2189 PAGE 823

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Oct. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner common to Sections 9, 10, 15 and 16, T 9 N, R 14 W
Post set by GLO Surveyors in 1837 : Ironwood 6" N38°E 18L & Beech 6" S3°E 10L

MCRC 1950's Witness Map shows : 3/4" I.P. - NE 58.90' 40" Oak - ESE 70.70' 20" Oak - WSW 95.95' Tw. M - NW 109.45' 16" M

Current
Current MCRC Witness Book shows 1 1/2" Iron - SE 44.09' St. Sign - NE 55.77' 40" Oak - NE 97.43' 36" Oak - NE 46.35' P.P. - NE 58.90' 40" Oak - ESE 70.70' 20" Oak - WSW 95.95' Tw. Map. - NW 109.45' 16" Map LCRC L-1118, P 938 in 1977 by C P Englert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe over 1" Pinched Pipe over Stone over 1" Pipe
Accepted corner based on Historical usage and Documentation

5 ✓
7/7/98

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1950

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- S 25° W 69.01' Found Spike in E side of 46" Oak
- S 76° W 94.30' Set Spike in SE side of 8" Ash
- N 67° W 65.93' Set Spike in N side of Twin 10" Ash
- N 25° W 72.30' Set Spike in E side of 8" Triple 8" Basswood
- N 25° E 55.75' Found Spike in W side of 58" Oak
- N 73° E 97.33' Set Spike in NW side of 46" Oak



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16946

Date Dec. 23, 1998

A 2000