

SURVEY & REMONUMENTATION

MAR 09 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1998 DEC 29 PM 4:24

For corners in SECTION

Muskegon

(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|---|------------|-----|
| 1. Public Land Survey | | T 9N R 14W | G-6 |
| | | T R | |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. Property Controlling In Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |

Carrie Carter
REGISTER OF DEEDS

LIBER 2189 PAGE 824

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Oct. 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Sections 15 and 16, T 9 N, R 14 W

Post set by GLO Surveyors in 1837 : Hemlock 10" N26°W 7L & Hemlock 8" N79°E 4L

1950'2 MCRC Witness Map shows nothing at this corner

Current MCRC Witness Book shows : 5/8" Iron F.F.S - NNE 17.45 CL St. Sign - NE 40.30' 8" Pop. - WSW 35.85' Tri. 6" Pop.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" Pipe over Plow Point

Accepted corner based on Historical Usage and Documentation

SV
7/7/98

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- N 36° E 40.30' Set Spike in SE side of 14" Poplar
- N 83° E 29.19' Set Spike in S side of multiple 6" Apple
- S 45° W 23.48' Set Spike in SE side of 10" Poplar
- S 68° W 35.85' Set Spike in N side of Triple 8" Poplar
- S 79° W 85.96' Set Spike in N side of 6" Poplar
- N 40° W 58.87' Set "PK" Nail in SW side of 4" Fence Post
- S 21° E 17.3'+ Found Street Sign



Signed by Ralph W. Van Riper

Date Dec. 23, 1998

Surveyor's Michigan License No. 16946

A 2001