

SURVEY & REMONUMENTATION

MAR 09 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1998 DEC 29 PM 4: 25

Carrie Carter
REGISTER OF DEEDS

For corners in **SECTION**

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>14</u> W	<u>H-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 2189 PAGE 828

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Oct. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Section 3, T9N R14W and Section 34, T10N R14W
 Post set by GLO Surveyors in 1837 : Sugar 12" N55°W ?L & Hemlock 10" N40°E ?L
 MCRC 1950's Witness Map : 2" Stake - ENE 66.80' 24" M - ESE 31.3' 14" Elm
 Current MCRC Witness Book : 3/4" Iron - N60°W 114.80' P.P. - S05°E 29.40' P.P. - NE 66.74' 36" Maple - SE 31.60' 24" Elm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4 Pipe and accepted corner based on Historical usage and documentation

*sw
7/7/98*

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap
 N 83° E 148.19' Set Spike in S Side of Twin 6" Ash
 S 69° E 91.43' Found Spike in SW Side of Utility Pole
 S 03° E 29.40' Found Spike in E Side of Power Pole
 S 66° W 207.24' NE Corner of Brick House
 N 83° W 265.48' Set Spike in S Side of 36" Maple
 N 56° W 114.54' Found Spike in SW Side of Power Pole



Signed by *Ralph W. Van Riper*
 Surveyor's Michigan License No. 16946

Date Dec. 23, 1998

A2005