

MAR 09 1999

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 1998 DEC 29 PM 4:25
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
Muskegon (County)

Carrie Carter
REGISTER OF DEEDS

LIBER 2189 PAGE 829

Register of Deeds Stamp & File Number

Located In:	Corner Code #
1. Public Land Survey T 9 N R 14 W	H-2
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous Property in Sec. S T R	
S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Oct. 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4					●	2	1			
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 3, T 9 N, R 14 W

Not set by GLO Surveyors

MCRC 1950's Witness Map and Current MCRC Witness Book shows nothing at this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Caped Rod set in 1996 by D G Sandel at intersection of Quarterlines
Accepted Corner as set (No witnesses by D G Sandel)

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

sw
7/7/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- N 05° E 34.06' Set Spike in W side of 4" Fence Post
- N 78° E 10.00' Set "PK" Nail in S side of 6" Fence Post
- S 01° W 92.90' Set Spike in E side of 10" Poplar
- S 40° W 131.28' Set Spike in E side of 8" Maple
- N 88° W 296.80' Set Spike in S side of 12" Poplar
- N 41° W 178.88' Set Spike in SW side of 8" Pine



Signed by Ralph W. VanRiper
Surveyor's Michigan License No. 16946

Date Dec. 23, 1998

A2006