

MAR 08 1999

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 DEC 29 PM 4: 25

For corners in

Muskegon

(County)

Located in:

Corner Code #

- 1. Public Land Survey T9N R 14W H-4
- T___ R___
- T___ R___
- T___ R___
- 2. Property Controlling S___ T___ R___
- in Section S___ T___ R___
- 3. Miscellaneous S___ T___ R___
- Property in Sec. S___ T___ R___

Carrie Carter
REGISTER OF DEEDS

LIBER 2189 PAGE 830

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	●	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 10, T 9 N, R 14 W

Not set by GLO Surveyors

MCRC 1950's and Current MCRC Witness Book shows nothing at this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" by 18" Steel Rod set at intersection of Quarterlines in 1993 by R W VanRiper
LCRC : L-1716, P-622, Accepted corner as set

sw
7/7/98

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- S 54° E 230.87' Set "PK" Nail in N side of Power Pole
- S 64° W 311.10' Set "PK" Nail in N side of Power Pole
- N 03° W 50.89' Found "PK" Nail in Top of 6" Fence Post
- N 73° W 64.65' Set Spike in S side of 5" Elm
- N 60° W 36.60' Set Spike in S side of Twin 4" Elm
- N 50° E 24.01' Set Spike in S side of 4" Poplar



Signed by *Ralph W. Van Riper*

Date Dec. 23, 1998

Surveyor's Michigan License No. 16946

A2007