

SUBJECT  
REMONSTRANCE

MAR 18 1939

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE 1998 DEC 29 PM 4: 25  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Muskegon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>14</u> W	<u>H-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

*Carrie Carter*  
REGISTER OF DEEDS

LIBER **2189** PAGE **831**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on Oct. 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5								●					
6		10	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Sections 10 and 15, T 9 N, R 14 W  
Post set by GLO Surveyors in 1837 : Beech 12" N34°W 10L & Beach 12" S47°W 11L

MCRC 1950's Witness Map shows : I.P. - N 29.43' 10" Th. A. - NE 131.76' 24" M. - WSW 102.4 T.

MCRC Current Witness Book shows : 1" Iron Pipe C.F.L. - NW 69.00' 19" Locust - ESE 71.8'  
Tw. Cherry - N 20" Thorn 28.91' - S 10" Pine 39.56' - SE 65.65' NW Cor. Fdn.  
LCRC L-1118, P-938 in 1977 by C P Englert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe, Accepted corner based on Historical Usage & Documentation.

*SW  
7/7/98*

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 2 3/4" Cast Iron Monument with County Survey Cap
- S 63° E 71.85' Found Spike in SW side of Triple 14" Cherry
- S 05° W 39.56' Found Spike in W side of 12" Pine 39.56'
- N 65° W 68.96' Found Spike in NE side of 18" Locust
- N 48° W 40.85' Set Spike on NE side of 12" Locust
- N 02° E 28.42' Set Spike in E side of 27" Locust
- N 57° E 69.36' Set Spike in W side of Multiple 6" Maples



Signed by *Ralph W. Van Riper*  
Surveyor's Michigan License No. 16946

Date Dec. 23, 1998

A2008