

MAR 09 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD
1998 DEC 29 PM 4: 26

Carrie Carter
REGISTER OF DEEDS

LIBER 2189 PAGE 832

Register of Deeds Stamp & File Number

For corners in

<u>Muskegon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>14</u> W	<u>H-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 15, T 9 N, R 14 W

Not set by GLO Surveyors

1950's MCRC Witness Map shown nothing at this corner

Current MCRC Witness Book shows : Set 1/2" Rod by Westshore - S 45° E 4" Ash 24.45' - S 10" Ash 35.60' - S 30° W 8" Ash 29.58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Westshore Capped Rod which was set at intersection of Quarter Lines.
Accepted corner as set.


sw
7/7/98

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- S 74° E 26.03' Set Spike in S side of 4" Ash
- S 47° E 27.71' Set Spike in NE side of 12" Ash
- S 15° E 22.93' Set Spike in E side of 4" Ash
- S 42° W 29.49' Set Spike in NW side of 16" Ash
- S 84° W 54.02' Set Spike in N side of 4" Ash
- N 37° W 52.42' Set Spike in SW side of 6" Ash



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16946

Date Dec. 28, 1998

A2009