

SURVEY &  
REMONSTRATION

MAR 09 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

1998 DEC 29 PM 4:26

For corners in

SECTION

Located In:	Corner Code #
<u>Muskegon</u> (County)	
1. Public Land Survey	T <u>9N</u> R <u>14W</u> <u>H-11</u>
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S ___ T ___ R ___
	S ___ T ___ R ___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

*Carrie Carter*  
REGISTER OF DEEDS

LIBER **2189** PAGE **834**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on Oct. 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Sections 27 and 34, T 9 N, R 14 W  
Post set by GLO Surveyors in 1837 : Maple 20" S18°W 16L & B Ash 8" N4°W 7L

MCRC 1950's Witness Map shows : I. Rod - N 25.6' F. Post - NE 61.10' 10" Ash - SSW 46.75' 3" Ash

Current MCRC Witness Map shows : Iron - with same Witness as 1950's Map

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4 Pipe, Accepted Corner based on Historical Usage and Documentation

*Sum*  
*7/7/98*

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- N 22° W 37.84' Set Spike in E side of 8" Ash
- N 01° E 37.63' Set Spike in W side of 8" Twin Ash
- N 62° E 61.08' Found Spike in SE side of 24" Ash
- S 56° E 80.46' Set Spike in NE side of 5" Maple
- S 17° E 39.11' Set Spike in E side of 6" Ash
- S 28° W 46.29' Found Spike in E side of 6" Twin Ash



Signed by *Ralph W. Van Riper*  
Surveyor's Michigan License No. 16946

Date Dec. 28, 1998

*A2011*