

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

For corners in

MUSKEGON
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 9N R 14W 1-6
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

1998 DEC 23 AM 8:11

Carrie Carter
REGISTER OF DEEDS

LIBER 2187 PAGE 892

Register of Deeds Stamp & File Number

I, STANLEY H. SHACKELFORD, in a field survey on JULY 7, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | |
|----------|--------------------------------|------------|-------------|
| I-6 1837 | G.L.O. set post. | | |
| | N 08° W | 9.90' | 12" Beech |
| | N 13° E | 7.26' | 6" Hemlock |
| 1950 Era | M.C.R.C. Tie Book, found iron. | | |
| | NW | 55.50' | 12" Willow |
| | ESE | 74.78' | Stump |
| | W | 33.00' | Iron |
| | Se | 49.50' | Street Sign |
| | Ne | 45.70' | Fence Post |
| W | 32.90' | Fence Post | |



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | | | | |
|-----|---|---------|------------|------------------|
| I-6 | Found capped rod in monument box #41107. Note...intersection recently redone and lowered 2-3'. Set 2 3/4" x 30" cast-iron county survey monument in monument box with county surveyor's cap. | | | |
| | N 49° W | 55.50' | 34" Willow | Found Nail |
| | S 17° E | 52.83' | S.C.I.R. | 1' E. Of Asphalt |
| | N 89° W | 32.94' | Angle Iron | Found |
| | N 61° E | 65.26' | 8" Spruce | Set Nail |
| | S 17° W | 247.45' | Power Pole | Found Nail |
| | N 78° W | 34.80' | 8" Pine | Found Nail |

Accepted position of corner due to historical usage and documentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | | |
|-----|--|---------|------------|--------------------|
| I-6 | Set 2 3/4" x 30" cast-iron county survey monument in monument box with county surveyor's cap | | | |
| | N 49° W | 55.50' | 34" Willow | Found nail NE side |
| | S 17° E | 52.83' | S.C.I.R. | 1' E Of Asphalt |
| | N 89° W | 32.94' | Angle iron | Found |
| | N 61° E | 65.26' | 8" Spruce | Set Nail |
| | S 17° W | 247.45' | Power Pole | Found Nail |
| | N 78° W | 34.80' | 8" Pine | Found Nail |

June 2 1998
POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

Signed by Stanley H. Shackelford Date 12-22-98
Surveyor's Michigan License No. 30100

A1967