

MAR 09 1999

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF MUSKEGON  
 RECEIVED FOR RECORD

1998 DEC 23 AM 8:11

For corners in **SECTION**

<u>MUSKEGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>1-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Carrie Carter*  
 REGISTER OF DEEDS

**LIBER 2187 PAGE 894**

Register of Deeds Stamp & File Number

I, STANLEY H. SHACKELFORD, in a field survey on JUNE 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1-9 G.I.O. in 1837 set post.  
 S 46° W 26.40' 22" Hemlock  
 N 58° W 11.88' 6' Beech

G.L.O. is 528' to stream South. 1950 era, M.C.R.C. tie book. Reset 1" iron pipe from County Survey #798 and Patterson Park survey #306 October 9, 1969, M.C.R.C.

Sw 42.00' 10" Red Pine  
 Se 33.85' Power Pole  
 Se 54.30' 10" Apple Tree  
 Ne 73.55' 14" Spruce

Charles F. Lewindowski.  
 N 86° W 26.80' Power Pole  
 S 33° E 53.65' 12" Apple  
 S 50° W 41.55' 12" Pine

Corner as found is 497', more or less, North of stream crossing.  
 Checked witnesses on Schiele survey R.P.S.-3817 recorded in Liber 1971, page 192.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1-9 Found 1"x21" pinched pipe. Set 2 3/4" x 31" cast-iron county surveyor's monument.

N 62° E 73.68'	18" Spruce	Found Nail	South Side
S 21° E 71.34'	6" Twin Elm (Dead)	Found Nail	West Side
N 85° W 27.03'	Power Pole	Found Nail	South Side
N 31° W 72.40'	12" Elm	Set Nail	East Side
S 70° E 151.49'	Power Pole	Set Nail	North Side
S 89° W 52.35'	10" - 12" Twin Ash	Set Nail	South Side

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1-9 Set 2 3/4" x 31" cast-iron county surveyor's monument.


N 62° E 73.68'	18" Spruce	Found Nail	South Side
S 21° E 71.34'	6" Twin Elm (Dead)	Found Nail	West Side
N 85° W 27.03'	Power Pole	Found Nail	South Side
N 31° W 72.40'	12" Elm	Set Nail	East Side
S 70° E 151.49'	Power Pole	Set Nail	North Side
S 89° W 52.35'	10" - 12" Twin Ash	Set Nail	South Side

Signed by Stanley H. Shackelford  
 Surveyor's Michigan License No. 30100

Date 12-2

*June 2 1998*

POSITION OF SAID  
 RECORDED CORNER  
 REVIEWED & RATIFIED  
 BY MUSKEGON COUNTY  
 PEER GROUP IN ACCORDANCE  
 WITH P.A. 345, OF 1990



A1969