

JAN 31 2001

LIBER 3124 PAGE 927

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

2001 DEC 29 AM 11:23

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mark Fairchild
REGISTER OF DEEDS

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 14W	J-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Quarter Section Post = Hemlock 12" N37°W 20L & Beech 8" S31°E 16L
1950's MCRC Witnesses Sheets show nothing at this Corner : Current MCRC Witnesses Book shows =
3/4" Iron : SE Tw 6" Elm 51.65' : WSW 6" Elm 29.95' : SE C of St Sign 48.40' : NE 87.30' P.P. :
NE 38.38' 14" Elm Stump : NW 54.43' Tel P : SE 77.97' Tel P M M Chambers found Iron in
1962 with the last 3 above witnesses C F Lewandoski Found an Iron in 1962 & 1963
F F Smith Found a 1" Solid Iron in 1968 D G Sandel in 1993 Found 1" Bent Iron Rod &
Replaced it with a Capped 5/8" Rod (# 25870) MCRC Replace 5/8" Capped Rod with a 2 3/4"
Cast Iron Monument & Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 3/4" Cast Iron Monument in a Monument Box in Centerline of Gravel of Adams Road,
Fence Line to the West and 16' North of Centerline of Cline Road to the East.

Historical usage, documentation and evidence of corner location review and ratified
by Muskegon County Peer Group 7/11/2000

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345 OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2 3/4" Cast Iron Monument in a Monument Box
S 60° E 99.33' Set "+" Cut on Top of E end of 18" Conc. Culvert
S 17° E 105.90' Set "+" Cut on Top of N end of 15" Conc. Culvert
S 12° W 115.92' Found Spike in E side of 14" Elm
S 88° W 62.87' Found Spike in N side of Dead Twin 6" Tree
N 37° E 46.66' Found Spike in NW Side of Wood Fence Post
N 66° E 85.60' Found Spike in S side of Power Pole



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date 12/26/00

A2199