

SURVEY & REMONUMENTATION

JAN 31 2001

LIBER **3124** PAGE **928**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

200 DEC 29 AM 11: 23

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Muskegon (County) | Located In: | Corner Code # |
|------------------------------------|--|---------------|
| 1. Public Land Survey | T <u>9</u> N R <u>14</u> W | K-2 |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |

Mark Fairchild
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W VanRiper, in a field survey on Dec. 18, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 16 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set 1/4 Section Post = Butternut 15" N37°W 40L & Elm 10" N21°E 67L

1950's MCRC Witnesses Sheets shows nothing at this corner : Current MCRC Witness Book = NNW 13.7' 16" Elm : NW 43.77' 18" Maple : SSW 25.55' 16" Elm : R W VanRiper & S V Vallier have Found & used this Corner

C F Lewandoski Found Iron in 1962 & 1964 : Consumers Power Co. Survey in 1968 shows Iron J C Bueche, LCRC in 1987, Found 3/4" Round Iron = Nail in W side of 18" Elm N0°E 13.66' : Nail in E side of 16" Dead Tree S10°W 25.19' : Nail in W side of 22" Elm N 20° E 55.43' : Nail in S side of 16" Elm N80°E 21.86' : Nail in SW side of 10" Elm N55°W 29.46'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe, No occupations line in any direction

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 7/11/2000

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

RWR
7/11/00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument

- N 55° W 29.46' Found Nail in SW side of 12" Elm
- N 10° W 13.59' Found Nail in W side of 22" Elm
- N 70° E 21.90' Found Nail in S side of 10" Elm
- S 60° E 30.43' Set Nail in N side of 8" Elm
- S 08° W 23.90' Set Nail in E side of 8" Elm
- S 85° W 25.15' Set Nail in Nly side of 7" Elm



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16948

Date 12/26/00