

SURVEY & REMONUMENTATION

LIBER 3124 PAGE 929

JAN 31 2001

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

2000 DEC 29 AM 11:23

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Musk Fairchild
REGISTER OF DEEDS

SECTION

For corners in

<u>Muskegon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>K-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ralph W VanRiper, in a field survey on Dec. 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO Set Section Post = Blue Beech 8" S54°W 38L & Ironwood 6" N48°W 26L

1950's MCRC Witness Sheets & Current MCRC Witness Book shown nothing at this Corner

J C Bueche, LCRC in 1987 Found 1/2" Round Iron = Nail in SE side of Twin 6" Oak N35°W 38.30' : Nail in W side of 10" Dead Tree N0°E 9.00' : Nail in W side of 8" Oak S45°E 14.39' : Nail in W side of 8" Oak S 45° E 14.39' : Nail in S side of 18" Oak N 40°E 36.58' : Centerline of Power Line N&S is West 100' : Nail in S side of Tri. 16" Oak N90°W 45.11' : Fence North

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Pipe & Old Fence Line North

Historical usage, documentation and evidence of corner location reviewed and ratified by Muskegon County Peer Group 7/11/2000

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

RWR *7/11/00*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron "County Survey" Monument

- N 50° W 38.20' Found Nail in SW side of Twin 10" Maple
- N 03° E 8.98' Found Nail in W side of 10" Dead Oak
- N 41° E 36.46' Found Nail in Sly side of 22" Oak
- S 49° E 14.35' Found Nail in W side of 12" Oak
- S 36° W 7.97' Set Nail in E side of 12" Oak
- N 79° W 44.61' Set Nail in N side of Triple 20" Oak



Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date 12/26/00