

FEB 09 2000

LIBER 2326 PAGE 785

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

1999 DEC 27 PM 12: 45

*Mark Fairchild*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in SECTION

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephen V. Vallier, in a field survey on December, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 G.L.O. (John Mullett) set the quarter section post.  
S 81° E 11 Links 6" Beech  
N 34° W 10 Links 6" Ironwood

1950's M.C.R.C.'s witness tie book notes an iron with no witness.

1984 C. F. Lewandowski found an empty monument box and set a 4" x 30" cast-iron monument. Recorded L.C.R.C. in Liber 1301, Page 606.  
East 66.20' 12" Elm  
N 50° E 44.26' 4" Elm  
N 25° W 68.21' 10" Elm  
S 85° W 67.20' Power Pole

**MARK F. FAIRCHILD**  
MUSKEGON COUNTY  
Register of Deeds  
Recorded Copy!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 2 3/4" cast-iron monument with a county surveyor's cap in a monument box on an old fence line to the east and a tree line to the west. Accepted the position of corner due to historical usage and documentation. Evidence is inconclusive that the corner is a correct and true perpetuation of the G.L.O. corner.

East 66.45' 12" Elm Stump  
S 85° W 67.20' Power Pole Found nail on west side

POSITION OF SAID  
RECORDED CORNER. *sw*  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 2 3/4" cast-iron monument with a county surveyor's cap in a monument box.  
East 66.45' 12" Elm Stump  
S 85° W 67.20' Power Pole Found nail on west side  
N 40° E 118.00' Telephone Pole Found nail on south side

North 2656.72' Distance to K-5  
South 2653.03' Distance to K-7



Signed by *Steph Vallier*  
Surveyor's Michigan License No. 28428

Date 12/22/99

A2074