

FEB 09 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1999
DEC 27 PH 12:44

Mark F. Fairchild
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in **SECTION**

Muskegon
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>9N</u>	R	<u>14W</u>	<u>L-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling In Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephen V. Vallier, in a field survey on December, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 G.L.O. (John Mullett) set the quarter section post.
S 9° W 8 Links 12" Maple
N 10° E 9 Links 10" Elm

1950's: M.C.R.C. notes a found iron in witness tie book.

1984 C.F. Lewandowski found a 3/4" iron pipe, reset with a 4" x 30" cast-iron monument recorded in L.C.R.C., Liber 1301, Page 607.
S 53.22' Power Pole
S 50° W 116.50' Telephone Pole
N 45° W 25.50' Telephone Pole

MARK F. FAIRCHILD
MUSKEGON COUNTY
Register of Deeds
Recorded Copy!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 4" cast-iron monument on tree row to the south. The corner is approximately 2' north of the north edge of an asphalt road and also appears to be the point of intersection of the roads. Accepted the position of corner due to historical usage and documentation. Evidence of corner being a perpetuation of the original G.L.O. position is non-supportive.

S 53.22' Power Pole
S 50° W 116.50' Power Pole Found nail on north side
N 45° W 25.50' Telephone Pole Found nail on northwest side

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990
8/10/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 4" cast-iron monument with county surveyor's cap. Corner is approximately 2' north of the north edge of asphalt road.
S 53.22' Power Pole
S 50° W 116.50' Power Pole Found nail on north side
N 45° W 25.50' Telephone Pole Found nail on northwest side



Signed by *Stephen Vallier*
Surveyor's Michigan License No. 28428

Date 12/22/99

A 206