

FEB 09 2000

LIBER 2326 PAGE 790

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

1999  
DEC 27 PM 12:45

Mark F. Fairchild  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 14W	L-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Stephen V. Vallier, in a field survey on December, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 G.L.O. (John Mullett) set the quarter section post.  
N 74° W 6 Links 10" Sugar  
S 38° E 34 Links 10" Beech

1977 C. Englert found a 1" iron pipe in monument box and recorded in L.C.R.C., Liber 1118, Page 937.  
N 85.25' Twin Elm

1984 C.F. Lewandowski found a 1" iron pipe in monument box, and reset with a 2 3/4" x 30" cast-iron monument, as recorded in L.C.R.C. in Liber 1301, Page 600.  
North 86.03' 8" Twin Elm  
N 80° E 149.25' 24" Maple  
South 15.75' 1/2" Iron Rod

**MARK F. FAIRCHILD**  
MUSKEGON COUNTY  
Register of Deeds  
Recorded Copy!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 2 3/4" cast-iron monument with a county surveyor's cap in monument box at the center line of road on the occupation line to the North. Accepted position of the found corner due to historical usage and documentation. Evidence is inconclusive that the corner is the correct and true perpetuation of the G.L.O. corner.

North 86.03' 12" Twin Elm Stump  
N 80° E 149.25' 24" Maple  
South 15.75' 1/2" Iron Rod

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 2 3/4" cast-iron monument with a county surveyor's cap in monument box in the center line of road.  
North 86.03' 12" Twin Elm Stump  
N 80° E 149.25' 24" Maple  
South 15.75' 1/2" Iron Rod  
East 2705.9' Distance to Corner M-7  
West 2647.4' Distance to Corner K-7



Signed by [Signature]  
Surveyor's Michigan License No. 28428

Date 12/22/99

A2079