

FEB 09 2000

LIBER **2326** PAGE **780**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1999 DEC 27 PM 12:45

Mark F. Fairchild
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephen V. Vallier, in a field survey on December, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 G.L.O. (John Mullett) set the quarter section post.
S 85° W 18 Links 22" Beech
N 44° W 42 Links 18" Sugar

1983 Ottawa County Surveyor (T. Joiner) found a 1/2" iron, and reset a 4"x30" cast-iron monument, as recorded in L.C.R.C., Liber 5, Page 145, Ottawa County Records.

1984 C.F. Lewandowski found a 4" cast-iron monument, as recorded in L.C.R.C., Liber 1301, Page 602 of Muskegon County Records.
East 56.10' Power Pole
S 75° W 33.74' 4" Triple Elm
S 25° W 69.54' 10" Basswood
N 35° E 34.54' 10" Basswood

MARK F. FAIRCHILD
MUSKEGON COUNTY
Register of Deeds
Recorded Copy!

POSITION OF SAID *8/10/99*
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a broken 4" cast-iron monument 1' below surface of gravel road. Fence line to the east. Accepted the position of 4" cast-iron monument due to historical usage and documentation. Evidence of corner position being a perpetuation of the original G.L.O. corner is un-supportive.
S 75° W 33.75' 10" Triple Elm Cluster Found nail on south side
S 25° W 69.54' 10" Basswood Found nail on south side

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a broken 4" cast-iron monument.
East 66.50' Power Pole Found nail on north side
West 29.60' C/L Telephone Riser (54.11')
S 75° W 33.75' 10" Triple Elm Cluster Found nail on south side
S 25° W 69.54' 10" Basswood Found nail on south side



Signed by *Stephen V. Vallier*
Surveyor's Michigan License No. 28428

Date 12/22/99

A2069