

FEB 09 2000

LIBER 2326 PAGE 778

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

1999 DEC 27 PM 12: 45

For corners in SECTION

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>14W</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Mark F. Fairchild*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Stephen V. Vallier, in a field survey on December, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 G.L.O. (John Mullett) set the quarter section post.  
N 37° W 20 Links 12" Sugar  
S 27° W 17 Links 12" Lynn

1984 C.F. Lewandowski, Muskegon County Surveyor, found stone, and reset a 4"x30" cast-iron monument, recorded L.C.R.C., Liber 130 Page 599, Muskegon County Records.  
N 53° W 35.40' 12" Twin Oak  
East 36.94' 30" Basswood  
S 33° E 50.20' 32" Oak  
West 38.53' 14" Basswood

1990 Ottawa County Surveyor (T. Joiner) found a cast-iron monument, as recorded in L.C.R.C., Liber 6, Page 113, Ottawa County Records.

**MARK F. FAIRCHILD**  
MUSKEGON COUNTY  
Register of Deeds  
Recorded Copy!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 4" cast-iron monument with a County Surveyor's Cap. Monument on tree row to the west and approximately 1' deep in the center line of gravel road. Accepted the position of corner due to historical usage and documentation. Evidence is non-supportive of this position being the perpetuation of the original G.L.O. corner.

N 53° W 35.40'	12" Twin Oak	Found nail on the southwest side
East 36.94'	30" Basswood (Dead)	
S 33° E 50.20'	32" Oak	Found nail on north side

POSITION OF SAID CORNER  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 4" cast-iron Monument with a County Surveyor's Cap.  
N 53° W 35.40' 12" Twin Oak Found nail on the southwest side  
East 36.94' 30" Basswood (Dead)  
S 33° E 50.20' 32" Oak Found nail on north side



Signed by Stephen Vallier  
Surveyor's Michigan License No. 28428

Date 12/22/99

A2067