

APR 28 1995

LIBER 1810 PAGE 612

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD

1994 DEC 29 AM 10:17

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> R <u>15</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Carrie Carter REGISTER OF DEEDS

A1636

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Stephen V. Vallier, in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO set corner
- 1977 E. Glaza - L.C.R.C. Liber 1026 Page 895
- 1982 C.F. Lewandowski - L.C.R.C. Liber 1242 Page 289 - Found 1 1/2" iron Pipe - also found 3/4" iron pipe 80.65' S (L. 1026, P. 895). Reset 1 1/2" iron pipe with 4" x 30" cast iron monument with County Survey Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" cast iron monument with County survey Cap. Also found 3/4" iron pipe 80.65' South of this corner. Neither corner can be traced to origins of perpetuation. Based on Glaza L.C.R.C. one cannot determine if corner was lost, obliterated or found. After review of evidence decision to hold cast iron monument as correct position due to GLO correlation to creek calls.

Sept 9, 1993 SW

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 315, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4" Cast Iron monument with County Survey Cap.
- S 86.65' 3/4" iron pipe (Liber 1026 Page 895)
- S 10 deg E 36.45' 14" maple (dead) with nail
- S 55 deg E 24.63' 21" maple with nail
- N 85 deg E 43.48' 20" Maple
- N 79.30' 22" Maple



Signed by Stephen Vallier Date Dec 27, 1994

Surveyor's Michigan License No. 28428