

**SURVEY & REMONUMENTATION**

*1871 Pg. 645*

**A1751**

APR 04 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*R.F.D*  
Also

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>15W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<b>SURVEY &amp; REMONUMENTATION</b>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>APR 04 1996</u>
	S _____ T _____ R _____	_____

INDEX  
JNOBL  
M-8  
TAN RIVER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**COMMISSION**

I, Stephen V. Vallier, P.S., in a field survey on December 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner	S 07 deg. W	35 Links	7" Beech
	N 35 deg. W	11 Links	6" Beech
1050's M.C.R.C. - iron	S	58.50'	Power Pole
	SE	82.73'	Fence Post
	NW	154.55'	15" Apple
1979 Recorded L.C.R.C. Liber 1050 Page 06. (see Exhibit "A")			

STATE OF MICHIGAN  
 COUNTY OF MUSKEGON  
 REGISTERED LAND SURVEYOR  
 1995 DEC 18 PM 4:18  
*Stephen V. Vallier*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap in Monument Box.

N 37 deg. W	154.55'	15" Apple (nail)
N 70 deg. E	68.40'	Telephone pole (nail)
N 40 deg. W	88.40'	10" Cherry (nail)
S 45 deg. E	85.83'	Telephone pole (nail)
S	44.95'	Power Pole (nail)
S 25 deg. E	53.40'	Westerly edge concrete post

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

*Nov 13, 1995*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap in Monument Box.

N 37 deg. W	154.55'	15" Apple
N 70 deg. E	68.40'	Telephone pole (nail)
N 40 deg. W	88.40'	10" Cherry (nail)
S 45 deg. E	85.83'	Telephone pole (nail)
S	44.95'	Power pole (nail)
S 25 deg. E	53.40'	Westerly edge concrete post
N 37 deg. W	154.55'	15" Apple (nail)



igned by Stephen V. Vallier Date 12/15/95  
urveyor's Michigan License No. 28428