

**SECURITY &  
REMONUMENTATION**

LIBER **1810** PAGE **604**

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:16

For corners in **COMMISSION**

*Carris Carter*  
REGISTER OF DEEDS

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> R <u>15</u>	<u>B-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*A1628*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	•		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Stephen V. Vallier in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO did not set corner

- 1950's M.C.R.C. Tie Map - iron
- 1977 E. Glaza - record survey Liber 1107 page 610 Rod in monument box
- 1984 C.F. Lewandowski - L.C.R.C. Liber 1290 Page 976 - Found 5/8" rod on top 1 1/4" iron pipe in monument box. Reset with 2 3/4" x 30" cast iron monument with County Survey Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 3/4" Cast Iron monument with County Survey Cap.  
Accepted position of corner due to evidence of Historical usage and consistent documentation.

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

*Sept 9 1993 JCL*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 3/4" Cast Iron Monument with County survey Cap.

- N 20 deg W 68.06' 16" Twin Cherry with nail
- N 15 deg E 66.48' 14" Twin Cherry with nail
- S 70 deg E 89.81' 24" Oak with nail
- S 29.28' Power Pole with nail
- S 55 deg W 68.50' 26" Oak with nail



Signed by *Stephen Vallier*  
Surveyor's Michigan License No. 28428

Date Dec 27, 1994