

APR 28 1995

LIBER 1810 PAGE 608

STATE OF MICHIGAN COUNTY OF MUSKEGON RECEIVED FOR RECORD

1994 DEC 29 AM 10:16

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon (County)

Located In:

Corner Code #

- 1. Public Land Survey T 9 R 15 C-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Carris Carter REGISTER OF DEEDS

A1632

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 3, column B.

I, Stephen V. Vallier, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO set corner
1950's M.C.R.C. Tie Map - witnesses only
1974 Prein & Newhof - Record survey Liber 1049 Page 553
1982 C.F. Lewandowski - L.C.R.C. Liber 1237 Page 429
Found 1" iron pipe in monument box. Reset with 2 3/4" x 30" cast iron monument with County Survey cap in monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 3/4" cast iron monument in monument box with County Survey Cap. Accepted position of corner due to evidence of Historical usage and consistent documentation.

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PLEN. GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

Apr 7 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 3/4" cast iron monument with County survey Cap in monument box.

- S 45 deg W 64.73' 14" Twin Oak with nail
S 30 deg W 59.33' 10" Oak with nail
N 48 deg E 45.00' Guy Pole with nail



Signed by [Signature]

Date Dec 27, 1994

Surveyor's Michigan License No. 28428