

SURVEY & REMONUMENTATION

R1871 Pg. 652

A1755

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Muskegon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>15W</u>	<u>C-8</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

SURVEY & REMONUMENTATION
APR 04 1996
COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 REGISTER OF DEEDS
 1995 FEB 19 PM 4:19
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephen V. Vallier, P.S., in a field survey on December 8, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner	N	10 Links	10" Beech
	S 77 deg. E	21 Links	10" Hemlock
1950's M.C.R.C. - Iron	NE	70.70'	Power Pole
	SE	57.36'	16" Tree
	SW	67.75'	12" Apple
(see Exhibit "A")	NW	52.30'	Twin Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap in Monument Box.

N 53 deg. E	45.75'	Utility Pole (nail)
N 75 deg. E	109.15'	Road sign
S 45 deg. E	56.50'	Stop sign
S 30 deg. E	56.00'	Stop sign
N 30 deg. W	82.57'	14" Pine (nail)
N 15 deg. W	55.90'	Stop sign

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

Nov. 13, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap in Monument Box.

N 53 deg. E	45.75'	Utility Pole (nail)
N 75 deg. E	109.15'	Road sign
S 45 deg. E	56.50'	Stop sign
S 30 deg. E	56.00'	Stop sign
N 30 deg. W	82.57'	14" Pine (nail)
N 15 deg. W	55.90'	Stop sign



igned by *Stephen Vallier* Date 12/15/95
 urveyor's Michigan License No. 28428

EXHIBIT "A"
C8 T9N R15W

1980 C. Shangraw - found 3/4" Iron. Recorded L.C.R.C. Liber 1191 Page 136.

S	4.60'	Centerline of pavement
N 20 deg. W	55.90'	Stop sign
S 30 deg. E	56.00'	Stop sign

1990 S. Shackelford - found 3/8" x 14" Iron Rod in Monument Box 4' North of centerline.
Recorded Liber 1523 Page 942. Reset with 4" x 30" Cast Iron Monument.

N 53 deg. E	45.75'	Utility Pole (nail)
N 75 deg. E	109.15'	Road sign
S 45 deg. E	56.50'	Stop sign
S 30 deg. E	56.00'	Stop sign
N 30 deg. W	82.57'	14" Pine (nail)
N 15 deg. W	55.90'	Stop sign