

**SURVEY & REMONUMENTATION**

APR 28 1995

LIBER 1810 PAGE 32

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

MUSKEGON

(County)

Located In:

Corner Code ##

- |                                    |       |       |     |
|------------------------------------|-------|-------|-----|
| 1. Public Land Survey              | T 9N. | R 15W | D-1 |
|                                    | T     | R     |     |
|                                    | T     | R     |     |
|                                    | T     | R     |     |
| 2. Property Controlling in Section | S     | T     | R   |
|                                    | S     | T     | R   |
| 3. Miscellaneous Property in Sec.  | S     | T     | R   |
|                                    | S     | T     | R   |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A1539

*Caroline Carter*  
REGISTER OF DEEDS

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD  
1991 DEC 27 AM 11:41

Register of Deeds Stamp & File Number

I, STEPHEN V. VALLIER, in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
GLO CORNER NOT SET

1991 C.P. ENGLERT, LBR. 1566, PG. 65  
ESE 33.68' 12" OAK  
SSE 43.35' 14" OAK  
SW 14.28' 15" OAK  
W 48.13' 18" PINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE-ACCEPTED POSITION OF FOUND CORNER - TRACED ORIGIN TO 1960 WHEN C.F. LEWANDOWSKI SET AS SINGLE PROPORTIONATE MEASURE  
ESE 33.68' 12" OAK  
SSE 43.35' 14" OAK  
SW 14.28' 15" OAK  
W 48.13' 18" PINE

*Sept 6 1994 SL*  
POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 3/4" X 30" CAST IRON MON. WITH COUNTY SURVEY CAP - REPLACED 1/2" IRON PIPE  
S 73° E 33.68' NAIL N. SIDE 12" OAK  
S 19° E 43.33' NAIL N. SIDE 18" OAK  
S 33° W 14.22' NAIL N. SIDE 16" OAK  
S 70° W 48.10' NAIL S. SIDE 18" W. PINE  
WEST 9.54' 1" IRON PIPE S 1/4 SECTION 32, T10N, R15W  
N 40° E 46.17' NAIL W SIDE 16" QUAD OAK

Signed by \_\_\_\_\_

Date Dec 27, 1994

Surveyor's Michigan License No. \_\_\_\_\_

